BRUHATH BANGALORE MAHANAGARA PALIKE,
Byataryanapura Division

(36)

Item No. 09

DRAFT TENDER SCHEDULE

Name of Work:- Providing RCC Drain in Main and Cross roads of Kalappa layout in Ward No 10.

Sl. No.	Quantity as per Sanctioned	Rate as per Sanctioned Estimate	Description	Unit	ORIGINAL / DUPLICATE RATES	
					Figures	Rs. In Words
1	805.20	42.77	Removing B.S. slab of Drain and stacking. (P No.24 / i 5.32 SR 2010-11)	Sqm		
2	724.68	129.60	KSRRB 300-1 : Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2m meters and an average lift upto 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications complete as per specifications. (P No.126 / i 19.1 SR 2010-11)	Cum		
3	120.78	3495.96	KSRB 4-1.3: Providing and laying in position plain cement concrete mix 1:4:8 using 40mm and down size graded granite metal machine, concrete laid in layers not exceeding 15 cms. Thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specification No.KBS 4.1, 4.2 (P No. 12 / i 4.3 SR 2010-11)	Cum		
5	2717.58	172.80	KSRB 4-6.4: Providing and removing centering,shuttering, strutting, propping etc.., and removal of form work for vertical surface such as walls at any thickness,including attached pilasters, buttresses,plinth and string courses cost of all materials,labour complete as per specifications. (P No. 14 / i 4.31 SR 2010-11)	Sqm		
6	241.56	5247.72	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of mix 1:1.5:3 with 20mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slab, staircase, lintels, retaining walls, walls (any thickness) includingattached pilasters, columns,piers, abutments, pillars,posts,struts, buttresses, string or lacing courses,parapets,coping, bed blocks, anchor blocks plain window cills,fillets etc.., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Specification No. KBS 4.1, 4.6 (P No. 12 / i 4.11 SR 2010-11)	Cum		
	362.34	87.26	KSRB 2.3 : Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20cms.in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5m including cost of alllabour complete asperspecifications. (P No. 6 Item No.2.10 PWD SR 2010-11)			

ಕಾರ್ಯಪಾಲಕ ಇಂಜಿನಿಯರ್
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ.
ಬೃ.ಬೆ.ಮ.ಪಾ. ಯಲಹಂಕ ವಲಯ
ಸಹಕಾರನಗರ. ಬೆಂಗಳೂರು-92.

7	181.17 181.17	5838.48	KSRB 4.9.2 : Providing T.M.T steel reinforcement for RCC work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and westage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. (P No. 16 Item No.4.46 PWD SR 2010-11)	Qntl		
9	805.20	57.00	Refixing stone slabs of drains and pointing in C.M. (1:3) (P No.24 / i 5.33 SR 2010-11)	Sqm		
10	579.79	80.14	Leadfor disposalof debris shall be payable at the following rates	Cum		

Executive Engineer
Byataryanapura Division
B.B.M.P., Bangalore.

"DTS approved"

09/09/11

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ
ಬೆಂಗಳೂರು-92